BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division

Schedule-B

NAME OF THE WORK: Improvements to drain 4th, 5th cross of Bhuvaneshwari Nagara at Bagalagunte in ward no. 14

Sl. No	Description of work	Unit	Qty	Rate quoted by the Contractor Sri M/s. Sri Venkateshwara Enterprises	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 metres and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. complete as per the direction of Engineer-in-charge of the work.	Cum	235.89	91.7	Rupees Ninety One and Seventy Paise Only
2	Removing B.S slab of Drain and stacking and Removing & Refixing stone slabs of drains and pointing in C.M (1:3) complete as per the direction of Engineer-in-charge of the work.	Sqm	253.26	154.33	Rupees One Hundred Fifty Four and Thirty Three Paise Only
3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth,including cost of all materials, labour HOM of machinery curing complete as per specifications. complete as per the direction of Engineer-in-charge of the work.	Cum	64.67	5442.77	Rupees Five Thousand Four Hundred Forty Two and Seventy Seven Paise Only
4	Providing a granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete for 7.5 cms thick complete as per the direction of Engineer-in-charge of the work.	Sqm	1013.04	702.29	Rupees Seven Hundred Two and Twenty Nine Paise Only
5	Providing a granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete for 10 cms thick complete as per the direction of Engineer-in-charge of the work.	Sqm	442.8	871.16	Rupees Eight Hundred Seventy One and Sixteen Paise Only
6	Providing two line dressing to granite stone slab/granite stone masonry as per specification complete as per the direction of Engineer-in-charge of the work.	Sqm	442.8	1016.53	Rupees One Thousand Sixteen and Fifty Three Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP

Scanned by CamScanner

7	Providing Edge machine cutting to Granite slabs as per specification and direction of engineer in charge of the work. complete as per the direction of Engineer-in-charge of the work.	Rmtr	2460	63.3	Rupees Sixty Three and Thirty Paise Only
8	Providing and constructing granite / trap/ basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing, complete as per specifications. complete as per the direction of Engineer-in-charge of the work.	Cum	4.05	5597.09	Rupees Five Thousand Five Hundred Ninety Seven and Nine Paise Only
9	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 kgs, with 20 mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @ 0.56 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation plinth and cills including cost of all materials, labour HOM of machinery curing complete as per specifications. complete as per the direction of Engineer-in-charge of the work.	Cum	70.89	5906.86	Rupees Five Thousand Nine Hundred Six and Eighty Six Paise Only
10	Providing and construction load bearing wall with solid concrete block of Size 400x200x200mm having block density not less than 1800kg/m3 having a minimum average compressive strength of 5.00 N/mm2 confirming to IS 2185 (Part 1) : 2005 and constructed CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges scaffolding, curing, hire charges of machineries etc., Complete as specification complete as per the direction of Engineer-in-charge of the work.	Sqm	750.4	1047.85	Rupees One Thousand Forty Seven and Eighty Five Paise Only
11	Supplying and fixing precast reinforced conceret slabs 10cm thick of mix M20 using 20mm and sownsize graded grantite metal using reinforecement 100mm dia steel at 150mm C/C both ways cost, transportation, hire charges of machinerym machine cuttng the vertical face to get plain even surface etc., complete with all lead and lift conveyance charges, labour charges inclusive of cost of all materials complete as per the direction of Engineer-in-charge of the work.	Sqm	401.4	1791.39	Rupees One Thousand Seven Hundred Ninety One and Thirty Nine Paise Only
12	Providing & fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite jelly 200mm & down size with steel reinforcement including formwork, lift charges, curing & concrete finished surface both sides etc,. And as per drawing & the direction of Engineer-in-charge (Data Rate approved) complete as per the direction of Engineer-in-charge of the work.	Sqm	9	5026.02	Rupees Five Thousand Twenty Six and Two Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP

Scanned by CamScanner

13	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. of size 450 x 200 x 400 mm complete as per the direction of Engineer-in-charge of the work.	Nos	2084	407.06	Rupees Four Hundred Seven and Six Paise Only
14	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after throughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. complete as per the direction of Engineer-in-charge of the work.	Sqm	422.1	29.08	Rupees Twenty Nine and Eight Paise Only
15	Providing and applying spary painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materiasl, labour, complete as per specifications. complete as per the direction of Engineer-in-charge of the work.	Sqm	422.1	73.81	Rupees Seventy Three and Eighty One Paise Only
16	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4KM	Cum	235.89	90.36	Rupees Ninety and Thirty Six Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP

Scanned by CamScanner